



Cite this: *Analyst*, 2021, **146**, 2186

ANFO vapour detection with conducting polymer percolation network sensors and GC/MS

Merel J. Lefferts, ^a Lisa H. Humphreys, ^b Nathalie Mai, ^b
 Krishnan Murugappan, ^{†a} Ben I. Armitage, ^a Jean-François Pons ^b and
 Martin R. Castell ^a

Ammonium nitrate mixed with fuel oil (ANFO) is commonly used in improvised explosive devices (IEDs). The development of ANFO vapour sensors that are small, inexpensive, and easy to use will enable widespread IED detection in the context of security and humanitarian demining. Because of concealment and the low vapour pressures of most explosive materials, achieving sufficiently high sensitivity and low limits of detection are some of the main challenges of explosives vapour detection. Here ANFO chemiresistive vapour sensors based on polypyrrole (PPy) percolation networks are presented and compared to gas chromatography-mass spectroscopy (GC/MS) results for ANFO. Improved sensitivities are achieved by using a polymer percolation network instead of a thin film for the gas sensors. Vapour concentrations are detected of 13–180 ppb of ammonia emitted by a variety of different ammonium nitrate-containing fertilisers and fertiliser-diesel mixtures.

Received 16th December 2020,

Accepted 9th February 2021

DOI: 10.1039/d0an02403a

rscl.li/analyst

Introduction

The detection of improvised explosive devices (IEDs) plays an important role in both security and humanitarian applications. Especially in developing countries where unexploded devices remain concealed due to past or current conflicts, cheap and reliable humanitarian demining remains a challenge. The most commonly used types of IEDs are based on easily accessible materials, such as ammonium nitrate/fuel oil (ANFO) mixtures and perchlorates.¹ Vapour sensing of ammonium nitrate/fuel oil (ANFO) is especially challenging because the fertilisers commonly used as the ammonium nitrate (AN) component are not volatile, although their decomposition products are,^{2,3} whereas fuel oils such as diesel are omnipresent and can cause a high false positive rate.

It is perhaps surprising that despite modern technologies sniffer dogs are still considered the gold standard in vapour sensing. However, depending on the working environment, it is not always practical or ethical to use sniffer dogs. Other traditional methods used in humanitarian demining, such as the

use of metal detectors, ground penetrating radar, and acoustic sensors are not always effective because of the large range of materials, shapes, and sizes of the containers used for IEDs, and the frequent absence of metal components.⁴ Vapour sensing methods based on for example mass spectroscopy,⁵ ultraviolet Raman spectroscopy,⁶ and nuclear quadrupole resonance,⁷ often require relatively large pieces of equipment and are therefore not practical for use in the field. Conducting polymer (CP) based chemiresistive sensors provide a potential solution because they can be used for stand-off detection, use relatively cheap materials, are operated at room temperature, allow for easy data processing, and are small.^{8,9} Polymer-based sensors have been investigated for a range of materials, including NO₂,^{10,11} NH₃,^{12–14} and nitro aromatic explosives.¹⁵ One recent example uses small scale fluorescence based detectors for ANFO and ammonium nitrate/nitro methane (ANNM) detection.¹⁶

Although CP-based chemiresistive vapour sensors are promising, achieving the sensitivities and limits of detection required for the detection of ANFO-based IEDs is challenging. Here we address that challenge by using sensors based on a percolation network of CPs, instead of a more traditional CP thin film design. Previous work, using polypyrrole (PPy) percolation networks between interdigitated Au electrodes with a 100 μm separation on a flexible PET substrate for NH₃ detection, has shown that with this approach the sensitivity is significantly improved.¹⁷ Sensors based on a percolation network

^aDepartment of Materials, University of Oxford, Parks Road, Oxford, OX1 3PH, UK.

E-mail: merel.lefferts@materials.ox.ac.uk

^bCentre for Defence Chemistry, Cranfield University, Defence Academy of the United Kingdom, Shrivenham, SN6 8LA, UK

[†]Current address: Nanotechnology Research Laboratory, Research School of Engineering, Australian National University, Canberra, ACT 2601, Australia.



of CPs operate in the steep part of the percolation curve, where a small number of interactions between the analyte gas and the CP lead to a large resistance change, resulting in a high sensitivity. Additionally, compared to the sensors described in ref. 17, changing the substrate from PET to glass demonstrates the potential for sensor incorporation into silicon-based technologies, and decreasing the electrode separation increases the efficiency of the sensor fabrication process because of the earlier onset of the percolation region. Furthermore, detecting unknown vapour concentrations emitted by solid or liquid samples, as opposed to known concentrations of pure gases from a cylinder, is an important step towards real world application of CP based sensors. Here we demonstrate ppb level sensing of ANFO vapour using percolation networks of PPy between Pt interdigitated electrodes on a glass substrate.

The sensor responses are compared to gas chromatography-mass spectrometry (GC/MS) results for the same analyte materials. GC/MS is an analytical technique frequently utilised to identify and quantify the individual volatile components within a material or mixture. First, the components of the mixture are separated based on their chemical properties and affinity for the stationary phase. Next, the components are broken down into ionised fragments which are then separated based on their mass-to-charge ratio.¹⁸ It is a technique regularly employed by forensic scientists, to identify unknowns in fire and explosive investigations,^{19,20} for drugs detection,²¹ for environmental analysis to assess levels of NO_x in the atmosphere or pollutants in ecosystems,²² as well as NH₃ detection.^{23,24}

Methods

Conducting polymer percolation network sensors

To create the sensors, commercially available Pt interdigitated electrodes (IDEs) with a 5 μm electrode separation on glass substrates (Micrux, Spain) were used after cleaning with concentrated nitric acid (HNO₃, 90%) followed by sonication in ethanol (C₂H₆OH, 99.8%), methanol (CH₃OH, 99.9%), and acetone (C₃H₆O, 99.8%). All solvents were purchased from Sigma-Aldrich (UK). Polypyrrole (PPy) was grown on the IDEs using electrochemical polymerisation from a solution of 0.01 M pyrrole (Sigma-Aldrich) and 0.1 M lithium perchlorate (LiClO₄, Sigma-Aldrich) in acetonitrile (C₂H₃N, Sigma-Aldrich).

The two connection pads of the IDEs were connected and together used as the working electrode. A Pt coil (BASi, USA) was used as the counter electrode and an Ag/AgCl (CH Instruments, USA) reference electrode was used. An Autolab PGSTAT204 potentiostat (Metrohm, Switzerland) and a PC with Nova 1.11 software were used to control and monitor the electrochemical polymerisation.²⁵ Using chronoamperometry, the potential between the working electrode and the reference electrode was kept at 1.0 V for 50 s, typically resulting in sensors with a starting resistance between 3 kΩ and 25 kΩ, which we know from previous work with Au IDEs on flexible PET substrates corresponds to the percolation region for PPy percolation networks.¹⁷ After PPy growth the sensors were p-doped using chronoamperometry, by holding them at 1.0 V in a monomerless 0.1 M LiClO₄ solution in acetonitrile for 60 s.

The sensors were exposed to NO₂ and NH₃ (both from 10 ppm in N₂ cylinders, BOC) as well as 7 different fertilisers with and without diesel (Sigma-Aldrich). The fertilisers were Nutribooster, EXTRAN, CAN27, SULPHAN, AXAN, Prilled N (YaraBela), and recrystallised Nutribooster (prepared at Cranfield University) (Table 1). The ANFO samples consisted of ~0.94 g crushed fertiliser and 0.06 mL diesel because this is the ratio most commonly used in IEDs.^{26,27} For safety reasons, the sample size was limited to 1 g for all fertiliser and ANFO samples, fertilisers and fuel oils were stored separately, and after use samples were kept in an excess of water for disposal. N₂ (BOC) was used to carry the vapours emitted by the solid and liquid samples into the sensor testing chamber and to further dilute the NO₂ and NH₃ (BOC).

The sensors were tested in a custom-made sensor testing chamber at atmospheric pressure and room temperature (Fig. 1). The total flow rate was kept constant at 500 sccm using mass flow controllers (Alicat). The sensing chamber has 2 gas inlets and 1 gas outlet. Gas inlet A is used for gasses and mixtures of gasses from cylinders; N₂, NO₂, and NH₃ in this case. Inlet B has a t-shaped glass attachment that can hold liquid and solid samples such as the fertiliser, ANFO, and diesel samples. An N₂ flow through the t-shaped attachment, over the top of the sample holder, is used to carry vapours emitted by the solid or liquid sample into the sensor testing chamber through gas inlet B. Between exposures to analyte vapours gas inlet B is closed and the N₂ flow is switched to gas inlet A. This makes it possible to clean the t-shaped attachment and change the solid or liquid sample between

Table 1 The commercial fertilisers used for sensor testing, and their N and SO₃ content by weight %

	Fertiliser name	Total nitrogen content (%)	Nitrate-N (%)	Ammoniacal-N (%)	SO ₃ (%)
A	Nutribooster	25	12.5	12.5	5
B	EXTRAN	33.5	16.9	16.6	0
C	CAN27	27	13.5	13.5	0
D	SULPHAN	24	12	12	15
E	AXAN	27	13.5	13.5	9
F	Prilled N	33.5	16.9	16.6	0
G	Recrystallised nutribooster	25	12.5	12.5	Unknown






Fig. 1 Schematic of the sensing chamber showing the position of the sensor, electrical feedthrough for resistance measurements, gas outlet, gas inlet A, and gas inlet B with the t-shaped attachment for solid and liquid samples; an ANFO sample in this example.

exposures without disrupting the continuous N_2 flow through the sensor testing chamber. To monitor the changes in the resistance of the sensor during exposure to the analytes, 1 V was applied to the sensor and the current was measured.

GC/MS

For the GC/MS measurements an Agilent gas chromatograph model 7890B equipped with a CTC PAL RSI autosampler

Table 2 The GC and MS conditions for ammonium nitrate and ANFO

GC parameters	AN	ANFO
Inlet temperature ($^{\circ}C$)	200	280
Injection volume (μl)	240	240
Oven temperature program	40 $^{\circ}C$ (hold for 1 min) to 150 $^{\circ}C$ @ 60 $^{\circ}C$ min^{-1} (hold for 2 min)	40 $^{\circ}C$ (hold for 1 min) to 270 $^{\circ}C$ @ 60 $^{\circ}C$ min^{-1} (hold for 7 min)
Carrier gas and flow rate	Helium @ 1.2 $ml\ min^{-1}$	Helium @ 1.2 $ml\ min^{-1}$
Spilt ratio	50 : 1	50 : 1
Run time (min)	10	18
MS parameters	AN	ANFO
Ionisation mode	EI	EI
Transfer line temperature ($^{\circ}C$)	150	270
Ionization source ($^{\circ}C$)	230	300
MS quadrupole ($^{\circ}C$)	150	200

system and connected to an Agilent 5977A mass spectrometer based on a quadrupole analyser was used. The headspace analyses were then performed with a Rtx-Volatile amines capillary column (60 m \times 0.32 mm ID \times 0 μm film thickness, Restek). The GC and MS conditions for AN and ANFO are described in Table 2. The mass spectrometer data were acquired in full scan mode set monitoring m/z range from 10 to 100 Da, at 70 eV MS ionization energy. Subsequently, the ammonia area peak was measured in selective ion monitoring mode to increase the sensitivity by monitoring the target ion at m/z 17 and the quan-




Fig. 2 (a) Sensing response to 1 g crushed fertiliser A (Nutribooster). The sensor was exposed twice for 5 minutes and left to recover under dry N_2 flow for 10 minutes between exposures. (b) Sensing response of the same sensor to 2 ppm, 1 ppm, 500 ppb, and 100 ppb NH_3 . (c) Sensing response of the same sensor to 500 ppb, 1 ppm, and 2 ppm NO_2 . (d) Percentage resistance change vs. NH_3 concentration for this sensor. The error bars give the standard deviation based on repeat measurements with the same sensor. Green indicates the start of fertiliser or ANFO vapour being carried into the sensing chamber by the N_2 flow and red indicates the switch to a pure N_2 flow without analyte vapour.



titation was obtained with an external standard method. The chromatographic conditions were managed *via* Chemstation software while the data were acquired and processed using MassHunter GC/MS Software from Agilent.

Headspace samples consisted of 1 g of ammonium nitrate or 1 g ANFO in a 10 mL headspace vial. Glass beads (4 mm diameter) were added to concentrate the headspace by reducing the available volume, but the glass beads were not desorbed into the inlet. The headspace was measured by adding water at room temperature and measuring the weight and using the corresponding density to calculate the available volume. The samples were sealed with an aluminium screw cap. The vials were incubated at 90 °C for 10 min with the agitator at 500 rpm on for 5 s and off for 2 s, to encourage more volatile components to be released into the headspace prior to sampling. The standard gas syringe on the GC/MS equipment was used to extract the headspace from the samples. The ammonia standard was made by repeatedly vacuuming and flushing an in-house GC vial with a certified ammonia gas. The 5-point calibration ranging from 6.5 ppm to 97.8 ppm was built by measuring the peak area at different split ratios.

Results and discussion

After sensor fabrication, each sensor was placed in the sensor testing chamber and left under N₂ flow until a stable resistance baseline was reached. Then 1 g fertiliser was placed in the t-shaped sample holder and N₂ was used to carry any vapours emitted by the fertiliser into the sensor testing chamber. Exposing the sensor to the fertiliser granules or prills in this way did not result in a measurable sensor response. However, when the fertiliser had been roughly crushed using a pestle and mortar before being placed in the t-shaped sample holder, a sharp increase in the resistance of the sensor was recorded (Fig. 2A). This is likely due to the highly porous nature of the fertiliser granules. Crushing the granules releases vapours stored in the pores, making it possible for the sensor to detect the fertiliser. Although crushing the granules also increases the exposed surface area of the AN fertiliser, we expect the effect of this on the amount of vapour released on the timescales of these experiments to be relatively minor. In a real-life ANFO detection scenario the vapour will be released gradually over time, and accumulate in the con-




Fig. 3 Typical GC/MS chromatograms, displaying counts vs. acquisition time for AN, AN with diesel (b) and AN with gasoline (c). Contributions from AN, such as NH₃, CO₂ and H₂O are indicated (a). The analytes associated with diesel elute much later than those of AN, meaning that the diesel does not interfere with the AN contributions.



tainer or space in which the explosive device is contained, creating the headspace sample. Crushing the granules speeds up the vapour release, making it possible to conduct the experiment on a time scale compatible with a laboratory experiment. The sensor response is reversible, as demonstrated by the increase in resistance, gradually returning to its baseline once the vapour source is removed.

The same sensor was also exposed to NO_2 and NH_3 , at known concentrations (Fig. 2B and C). The PPy based sensor responds to both NO_2 and NH_3 , however the type of response shown for the two gases is different. Upon exposure to NO_2 the

resistance of the sensor increased slowly and irreversibly. Exposing the sensor to NH_3 resulted in a rapid and reversible increase in resistance because NH_3 is a strong electron donor and causes a decrease in the majority charge carrier in p-type PPy.²⁸ This is in agreement with previous results for higher concentrations of NH_3 .^{29,30} The type of resistance change measured when the sensor is exposed to NH_3 looks very similar to that obtained for the crushed fertiliser. Ammonium nitrate (AN) itself is not volatile. However, it slowly degrades into NH_3 and HNO_3 , resulting in vapour pressures similar to those of TNT.² Therefore it is likely that when detecting the crushed fertiliser sample, the sensor is in fact responding to the emitted NH_3 . Using a calibration curve based on the sensor response to known NH_3 concentrations it is possible to estimate the concentration of the NH_3 measured when detecting the fertiliser sample (Fig. 2D). Using the calibration curve we can say that in the example given in Fig. 2A approximately 180 ppb was detected.

It was also found that our sensors do not respond to diesel, one of the materials most commonly used as the fuel oil component of ANFO. Since diesel can be a common background signal in the types of environments in which an ANFO sensor would be implemented, such as buried roadside locations, the lack of response of the sensor to diesel vapour is an advantage because it decreases the number of false positives.

To be able to compare the sensor responses to an established analytical method, GC/MS was used to analyse AN and ANFO samples based on the same fertilisers. Like in the case of our percolation sensors, the GC/MS results confirm that the presence of diesel or gasoline does not significantly




Fig. 4 Sensing response to 1 g crushed fertiliser A, Nutribooster, (first peak) and 1 g ANFO consisting of 94% crushed fertiliser A and 6% diesel (second peak). The sensor response to the fertiliser and the ANFO are indistinguishable within error. Here green indicates the start of fertiliser or ANFO vapour being carried into the sensing chamber by the N_2 flow and red indicates the switch to a pure N_2 flow without analyte vapour.




Fig. 5 Sensing response of one sensor to a series of exposures to 1 g of each crushed fertiliser and 1 g ANFO made with each different fertiliser, consisting of 94% crushed fertiliser and 6% diesel. Where green indicates the start of fertiliser or ANFO vapour being carried into the sensing chamber by the N_2 flow and red indicates the switch to a pure N_2 flow without analyte vapour. For each different fertiliser the sensor response to the fertiliser and the ANFO are very similar. Furthermore, the sensing response is different for different fertilisers. At the end of the series the sensor was again exposed to 1 g of the first fertiliser as a control experiment to check that the sensor had not degraded during the series of exposures. The result indicates good sensor stability over time and after multiple exposure and recovery cycles.



Analyst

interfere with the detection of NH_3 in the GC/MS measurements (Fig. 3). This suggests that the fuel oil component, independent of which fuel oil is used, does not affect ANFO detection.

Next, 4 different PPy percolation network based sensors were exposed to 7 different fertilisers and ANFO mixtures based on those fertilisers. The AN to FO ratio typically used in ANFO-based IEDs is 94% AN and 6% FO,^{26,27} therefore ~ 0.94 g crushed fertiliser was mixed with 0.06 mL diesel. As expected, the increase in sensor resistance is rapid and reversible for all fertiliser and ANFO samples. For each fertiliser the sensors were first exposed to 1 g crushed fertiliser and then to 1 g ANFO made with the same fertiliser. The typical sensor responses to a fertiliser and its ANFO shown in Fig. 4 correspond to 170 and 177 ppb NH_3 respectively. The sensing responses to the fertilisers and the ANFOs were indistinguishable within error, as shown by the typical raw sensor responses shown in Fig. 4 and raw responses for 7 different fertilisers (Fig. 5) and a summary of responses of multiple sensors to 7 different fertilisers (Fig. 6). This is as expected because the sensors are sensitive to the fertilisers but not to the diesel. This also implies that if any vapour components exist that are unique to the ANFO mixture, they are not detected by our sensors. However, to our knowledge, such components have not been described in the scientific literature.

Each of the 4 sensors was subjected to a series of consecutive exposures to the 7 different fertilisers and ANFO mixtures based on those fertilisers (Fig. 5). At the end of each series the sensor was exposed to the first fertiliser from the series for a second time, as a control experiment, to check that the sensor had not degraded during the experiment. The first exposure to fertiliser A and the control experiment in Fig. 5 correspond to the detection of 171 and 216 ppb NH_3 respectively. This control experiment demonstrates that the sensors have good stability over time and after multiple exposure and recovery cycles. The series of exposures shows that, while the responses to a fertiliser and the ANFO made with the same fertiliser are very similar, the sensor responds differently to different fertilisers or ANFOs based on different fertilisers.

A series of exposures to the 7 different fertilisers and their ANFOs, as shown in Fig. 5, was repeated with 4 different sensors. A comparison between the 7 different fertilisers shows clear differences between the sensor responses to these fertilisers, with fertiliser A giving the strongest response (Fig. 6A). A similar pattern was observed when comparing the GC/MS results for the 7 different fertilisers and their ANFOs (Fig. 6B). One would expect that the AN content, and therefore the concentration of its decomposition product NH_3 , would directly influence the magnitude of the sensing response to each fertiliser. However, although the fertilisers have different compositions, the observed differences in sensor response cannot be explained by the nitrogen content of the fertilisers (Table 1). It is possible that other components impact the level of NH_3 that is detected. Additives that behave as desiccants




Fig. 6 Comparison of the sensor responses in ppb (a) and GC/MS results in ppm (b) for various fertilisers and ANFO mixtures. The results are averages of 4 different sensors for the fertiliser exposures and 3 different sensor for the fertiliser-diesel mixture exposures (a), and 3 GC/MS measurements (b). The error bars represent the standard deviation. The equivalent vapour concentrations in ppb or ppm were calculated using a calibration curve of sensor responses and GC/MS measurements of known NH_3 concentrations, respectively. The comparison between the responses to the fertilisers and ANFO mixtures shows that there is little difference between the response to a fertiliser and ANFO made with the same fertiliser. Furthermore, it shows clear differences between the different fertilisers. The pattern of which is similar for the sensor responses and the GC/MS measurements.

can prevent or slow down the breakdown of AN based fertilisers by removing moisture. Even in small quantities around 0.1% of common additives such as magnesium nitrate play an important role in the stability of the fertiliser.³¹ Additionally, it is possible that the porosity of the granules affects the amount of NH_3 released and therefore the magnitude of the sensor response. The relationship between sensor response and granule porosity could provide valuable information for sensing applications because porosity is known to be one of the most important factors determining explosives properties such as detonation velocity.²⁷

Because the sensors are based on percolation networks of PPy, a small variation in the PPy network can cause a relatively large change in the starting resistance and the sensitivity of the sensor, even for sensors produced using the same electrochemical recipe. This large effect caused by a small change in



the network is the same phenomenon that causes the high sensitivity and is therefore inherent to the sensor. However, by calibrating each sensor, using known NH_3 concentrations, each sensor can be used accurately and independently. Based on the calibration curve, the average sensing responses in Fig. 6A correspond to ~ 13 – 176 ppb. This is significantly lower than NH_3 and ANFO sensitivities previously reported in the literature using CP thin film based vapour sensors.^{13,14,29,32} The average amount of NH_3 measured in the GC/MS experiments in Fig. 6B corresponds to ~ 37 – 686 ppm. Although the sensor and GC/MS measurements were conducted under different experimental conditions and due to the limitations of the GC/MS equipment the average concentrations measured are significantly different, the comparison of the 2 methods demonstrates that both the patterns between different fertilisers and the similarity between the responses to a fertiliser and its ANFO is independent of the method. Furthermore, being able to detect much lower concentrations while operating at room temperature demonstrates the effectiveness of the percolation sensor.

Finally, it is important to note that the ANFO samples used in these experiments were only 1 g. ANFO-based IEDs detected in the field are likely to contain at least 1 kg ANFO,³³ but due to safety constraints it was not possible to test our sensors in the presence of such large ANFO samples. However, it is expected that our sensors will give a much larger response to larger samples, similar to the elevated responses measured for increased ammonia concentrations. This larger response will also help compensate for any decreases in response due to for example concealment or interference of others vapours present in the environment.

Conclusions

In conclusion, sensors based on a percolation network of PPy on interdigitated electrodes were successfully used to detect various AN containing fertilisers and ANFO mixtures. The sensor response, an increase in resistance, was rapid and reversible. The high sensitivities achieved with this sensor design offer a significant improvement compared to previously reported CP-based explosives vapour sensors. Additionally, measuring vapour concentrations emitted from ANFO mixtures directly is an enabling step towards real-world IED detection. The sensor results were validated by GC/MS results for the same fertilisers and ANFOs, revealing similar patterns in response to the various samples assessed. Future work is aimed at the practical implementation of this sensor by developing an integrated device and investigating the effects of concealment. Environmental factors such as temperature, humidity and other vapours have to be taken into account, either by recalibrating for real world conditions or by using an electronic nose type set-up. Taking these factors into account as well as incorporating a different sampling method can further improve the sensor performance.

Conflicts of interest

There are no conflicts to declare.

Acknowledgements

We are grateful to Professor Cesar Sierra for his advice. We thank Yara UK for providing the fertilisers. This work was supported by the EPSRC Global Challenges Research Fund. The GC/MS work was supported by the British Council Newton Fund.

References

- 1 C. Kopp, *Def. Today*, 2008, **4649**, 46–49.
- 2 F. L. Steinkamp, B. Giordano, G. Collins and S. Rose-Pehrsson, *Propellants, Explos., Pyrotech.*, 2015, **40**, 682–687.
- 3 J. C. Oxley, J. L. Smith, E. Rogers and M. Yu, *Thermochim. Acta*, 2002, **384**, 23–45.
- 4 J. M. Hendrickx, A. Molina, D. Diaz, M. Grasmueck, H. Moreno and R. Hernández, *SPIE Def. Secur. Symp.*, 2008, **6953**, 9.
- 5 V. V. Hernandez, M. F. Franco, J. M. Santos, J. J. Melendez-Perez, D. R. d. Morais, W. F. d. C. Rocha, R. Borges, W. de Souza, J. J. Zacca, L. P. L. Logrado, M. N. Eberlin and D. N. Correa, *Forensic Sci. Int.*, 2015, **249**, 156–164.
- 6 P. Jander and R. Noll, *Appl. Spectrosc.*, 2009, **63**, 559–563.
- 7 T. N. Rudakov, *Appl. Magn. Reson.*, 2012, **43**, 557–566.
- 8 B. Lakard, S. Carquigny, O. Segut, T. Patois and S. Lakard, *Metals*, 2015, **5**, 1371–1386.
- 9 M. J. Lefferts and M. R. Castell, *Anal. Methods*, 2015, **7**, 9005–9017.
- 10 M. K. Ram, O. Yavuz and M. Aldissi, *Synth. Met.*, 2005, **151**, 77–84.
- 11 K. Dunst, J. Karczewski and P. Jasiński, *Sens. Actuators, B*, 2017, **247**, 108–113.
- 12 Y. Wang, W. Jia, T. Strout, A. Schempf, H. Zhang, B. Li, J. Cui and Y. Lei, *Electroanalysis*, 2009, **21**, 1432–1438.
- 13 P.-G. Su, C.-T. Lee and C.-Y. Chou, *Talanta*, 2009, **80**, 763–769.
- 14 T. A. Ho, T.-S. Jun and Y. S. Kim, *Sens. Actuators, B*, 2013, **185**, 523–529.
- 15 S. J. Toal and W. C. Trogler, *J. Mater. Chem.*, 2006, **16**, 2871–2883.
- 16 S. Sheykhi, L. Mosca and P. Anzenbacher, *Chem. Commun.*, 2017, **53**, 5196–5199.
- 17 B. I. Armitage, K. Murugappan, M. J. Lefferts, A. Cowsik and M. R. Castell, *J. Mater. Chem. C*, 2020, **8**, 12669–12676.
- 18 H.-J. Hübschmann, *Handbook of GC/MS*, Wiley Online Library, 2000.
- 19 P. Suppajariyawat, M. Elie, M. Baron and J. Gonzalez-Rodriguez, *Forensic Sci. Int.*, 2019, **301**, 415–425.
- 20 A. Chakraborty, S. Bagchi and S. C. Lahiri, *Aust. J. Forensic Sci.*, 2015, **47**, 83–94.



- 21 H. H. Maurer, in *Acta Medicinæ Legalis Vol. XLIV 1994*, Springer, 1995, pp. 489–492.
- 22 C. J. Kirchmer, M. C. Winter and B. A. Kelly, *Environ. Sci. Technol.*, 1983, **17**, 396–401.
- 23 A. L. Lubrano, B. Andrews, M. Hammond, G. E. Collins and S. Rose-Pehrsson, *J. Chromatogr. A*, 2016, **1429**, 8–12.
- 24 C. J. Katilie, A. G. Simon and L. E. DeGreeff, *Talanta*, 2019, **193**, 87–92.
- 25 K. Murugappan and M. R. Castell, *Electrochem. Commun.*, 2018, **87**, 40–43.
- 26 J. Rowland and R. Mainiero, *Proc. Annu. Conf. Explos. Blasting Tech.*, 2000, **1**, 163–174.
- 27 B. Zygmunt and D. Buczkowski, *Propellants, Explos., Pyrotech.*, 2007, **32**, 411–414.
- 28 H. Bai and G. Shi, *Sensors*, 2007, **7**, 267–307.
- 29 H. Kharat, K. Kakde, P. Savale, K. Datta, P. Ghosh and M. Shirsat, *Polym. Adv. Technol.*, 2007, **18**, 397–402.
- 30 S. Carquigny, J.-B. Sanchez, F. Berger, B. Lakard and F. Lallemand, *Talanta*, 2009, **78**, 199–206.
- 31 H. Kiiski, PhD Thesis, University of Helsinki, 2009.
- 32 T. Shimanouchi, S. Morita, H.-S. Jung, Y. Sakurai, Y. Suzuki and R. Kuboi, *Sens. Mater.*, 2004, **16**, 255–265.
- 33 L. Figuli, Z. Zvaková, V. Kavický, S. Jangl and M. Vandlícková, *Sci. Mil. J.*, 2016, **11**, 34.

